Abstract quantities for constructing a Local Fund Dispensary Building at Hura, Nanjangud Taluk.

No.	Items of work	Per	Rate			Quantity
			Rs.	a.	p.	
	Dispensary—					
1	Earthwork excavation	C. yd.				74
2	Brick in mortar	C. ft.				4,999
3	Brick in mortar, arch work	"				99
4	Burnt stone slabs, 6" thick, dressed	S. ft.				350
5	Cut stone pillars with capitals	Each				10
6	Masonry mouldings at ends	"				2
7	Plastering with mortar	Sq.				39·26
8	Whitewashing	"				23·39
9	Colourwashing	"				15·87
10	Teakwood pannelled door without bottom rails with hinges, etc.	S. ft.				126
11	Windows with iron bar, ¾" diameter, pannelled with hinges, etc., complete.	"				52
12	Windows with iron bar with glazed shutters, etc., complete	"				30
13	Ventilators with glazed shutters, etc., complete	C. ft.				27
14	Circular ventilators do do	"				13
15	Teakwood wrought and put up	C. ft.				115·72
16	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sq.				19·20
17	Ridge tiles set in mortar	R. ft.				80
18	Zinc sheet for valley	S. ft.				44
19	Teakwood planks, 1" thick	"				44
20	Eave board, 9" high, ornamental	R. ft.				262
21	Cornice, 3" complete	"				25
22	Wood oiling, 2 coats	Sq.				18·15
23	Chocolate painting	"				8·89
24	Teakwood finials	Each				4
25	Teakwood shelf planks, 1½" thick	S. ft.				87
26	Flooring with 9" square Mangalore tiles, over 3" concrete and cement pointing.	Sq.				4·27
27	Flooring with Kadappa slabs, over 3" concrete and cement pointing.	"				4·61
28	Constructing cisterns	Each				2
29	Clearing site	L. S.	Rs.			
	Kitchen—					
1	Earthwork excavation	C. yd.				4
2	Brick in chunam					454
3	Burnt stone slabs, 6" thick, dressed	S. ft.				23
4	Plastering with chunam	Sq.				5·83
5	White and colourwashing	"				5·83
6	Teakwood battened doors, complete	S. ft.				18
7	Teakwood battened windows with iron bars, complete	"				4½
8	Teakwood wrought and put up	C. ft.				7·97
9	Roofing with first class Mangalore tiles, over teak reepers, etc., complete.	Sq.				2·29
10	Ridge tiles set in mortar and cement pointed	R. ft.				15
11	Teakwood eave board, plain, 6" high	"				60
12	Wood oiling, two coats	Sq.				0·74
13	Chocolate painting	"				1·05
14	Flooring with Kadappa slabs over 3" concrete and cement pointing.	"				0·32
15	Constructing oven and cisterns	L. S.	Rs.			
16	Ventilating tiles for kitchen	Each				4
	Latrine—					
1	Earthwork excavation	C. yd.				4
2	Burnt brick in mortar	C. ft.				362
3	Coping with burnt brick in mortar plastering, complete	R. ft.				40
4	Plastering with mortar	Sq.				4·26
5	Tarring	"				1·08
6	Flooring with Kadappa slabs over, 3" concrete and cement pointing.	"				0·63

V. V. KARVE,
Executive Engineer.

KADUR DISTRICT.

Dated 24th November 1921.

1. Notice is hereby given that sealed tenders will be received at the office of the Deputy Commissioner, Kadur District,—up to 15th December 1921,—for restoring Mugali Tank, Tarikere Taluk. An approximate estimate of quantities is noted overleaf. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's office at Chikmagalur, between the hours of 2 and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the from given below, showing the rates at which different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tenders for restoring Mugali Tank, Tarikere Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender thereof will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Description of work	Per	Quantity
Bund—		
Earthwork including watering and tamping, etc., complete	C. yd.	3,069
Puddle wall with good clay and gravel		73
Turfing to slopes	Sq. yd.	3,916
New stone revetment	C. yd.	147
Grade stones	Each	60
Index stones	...	60
B. M. stones	...	2
Registered No. stone	...	1
Weir at left 110 feet long—		
Earthwork	C yd.	25
Surki concrete	C. ft.	193
Burnt brick in surki mortar	"	555
4" burnt stone slabs for coping	S. ft.	166
Surki plastering	Sq.	6·00
Dry stone work	C. yd.	118
Draught clearing (hard soil)	"	82
Weir at right 160 feet long—		
Earthwork	C. yd.	263
Surki concrete	C. ft.	185
Burnt brick in surki mortar	"	131
Surki plastering	Sq.	50
4" burnt stone slabs	S. ft.	180
Dry stone work	C. yd.	3
Sluice—		
Repairing the present sluice	Lump sum	80

M. J. SAMPATKUMARACHAR,
For *Deputy Commissioner.*

MISCELLANEOUS DEPARTMENTS.

THE MYSORE DISTILLATION AND IRON WORKS.

FOR SALE.

Single Cylinder Horizontal Steam Engine by Davey Paxman & Co.

Diameter of Cylinder	14·75"
Stroke	24"
Diameter of Crank Shaft	5"
Diameter of Fly wheel	11'—0" smooth face.
Type of Sole Plate	C. I.
Governor	Gear Driven.
Valve gear	Slide expansion on governor.

Engine available for inspection at any time. Apply to Mysore Distillation and Iron Works, Bhadravati, Shimoga District (Mysore Railways).

C. A. RICHARDSON,
General and Construction Superintendent.